ATLAS Tile Calorimeter upgrade for the high luminosity LHC

Oleg Solovyanov on behalf of the Tile Calorimeter community

Outlook

- LHC
- ATLAS and Tile Calorimeter
- HL-LHC
- Tile Calorimeter upgrade
- Future accelerators
- Summary

Large Hadron Collider

Superconducting Proton Accelerator and Collider installed in a 27km circumference underground tunnel (tunnel cross-section diameter 4m) at CERN

Tunnel built for LEP e+e- collider in 1985

Design parameters: c.m. energy = 14 TeV luminosity = 10³⁴ cm⁻²s⁻¹ 1.15x10¹¹ p/bunch 2808 bunches/beam

Achieved by the end of 2017: c.m. energy = 13 TeV Inst. lumi 2.09x10³⁴ cm⁻²s⁻¹ 1.35x10¹¹ p/bunch 2544 bunches/beam ~80 <mu> 5+ fb⁻¹/week



LHC Experiments



• LHC Days in Belarus 2018

27.02.2018 • 4

ATLAS Detector



ATLAS Detector



• LHC Days in Belarus 2018

ATLAS Calorimeters



Tile Hadron Calorimeter



- Hadron non-compensating sampling calorimeter
 - Steel as radiator
 - o Scintillating tiles as active medium
- 3 mm thick scintillating tiles (PSM, BASF polystyrene + dopants) oriented perpendicular to beam axis, wrapped in Tyvek paper
- Readout via green WLS fibres (Kuraray Y11) connected to both short edges of scintillating tiles
- Hamamatsu R7877 PMTs, located in a module's girder, collect light from the fibre bundles
- 3 cylinders: EB-A, LB, EB-C
- 64 modules in a cylinder
- One module weighs 22 tons (LB)



- Long barrel $|\eta| < 1.0$, extended barrel 0.8 < $|\eta| < 1.7$
- WLS fibre routing defines calorimeter cells
- 0.1x0.1 $\Delta\eta x \Delta \phi$ cell granularity (0.2x0.1 for D layer cells)
- Three longitudinal layers, total thickness of about 7λ
- Pseudo-projective towers for first level trigger
- Design resolution for jets $\Delta E/E = 50\%/\sqrt{E+3\%}$

Calorimeter module



Instrumentation of the Tile Calorimeter barrel modules

• LHC Days in Belarus 2018

27.02.2018 • 10

Calorimeter in the cavern



Barrel calorimeters moved to Z=0

• LHC Days in Belarus 2018

Calorimeter in the cavern



Engineers working near Extended Barrel calorimeters

• LHC Days in Belarus 2018

27.02.2018 • 12

Calorimeter in the cavern



Extended Barrel calorimeters being moved to final position

• LHC Days in Belarus 2018

Front-end electronics



- PMTs signals are shaped and amplified with two gains (1:64)
- Analogue tower sums are provided for level one trigger
- Both gains are digitized in parallel by 40 MHz sampling 10-bit ADCs
- Digitised samples are temporary stored in pipeline memory
- Upon first level trigger decision the data of one of the gains are transferred to de-randomiser memory and then to the back-end electronics via readout fibres

Front-end electronics drawer



- Up to 45 PMT Blocks with HV bases
- Up to 45 3-in1 cards (shaper-amplifierintegrator board)
- 4 motherboards
- 8 digitizer boards
- one optical interface board
- one TTC receiver mezzanine card
- up to 10 analog summing cards
- one integrator readout board
- HV distribution boards
- LV distribution and sense adapters



Signal reconstruction

- Signal is reconstructed from 7 samples using optimal filtering
- Energy, time and quality factor are extracted from the sampled signal
- Amplitude of the signal is proportional to the energy (shaping)



Calibration systems



- To provide correct energy and time for data reconstruction an elaborate chain of calibration systems has been conceived:
 - Charge inject system (CIS) to calibrate the response of the ADC
 - Laser calibration system to measure the performance of the PMTs
 - Cesium moving radioactive source system to calibrate the full optical path from scintillating tiles and WLS fibres down to integrated current of the PMT
 - Minimum bias monitoring system (MBM) to monitor the response of the calorimeter online
- About 11% of 192 Tile calorimeter modules were calibrated at the test beams and the EM scale was transferred to the final detector with the help of calibration systems

FE electronics maintenance

- During shutdown, when ATLAS detector is opened
- FE electronics "drawers" are extracted and bad components are replaced or fixed
- Allows to operate with minimum number of bad channels to maximize the quality of the data
- Data quality from consolidates modules is checked and the progress – is tracked with web tools





Upgrade

HL-LHC





Goals of HL-LHC project:

 Prepare machine for operation beyond 2025 and up to 2039

LHC IntL (fb^-1) HL-LHC IntL (fb^-1)

- 250 300 fb⁻¹ per year
- 'ultimate' performance of 7.5 10³⁴ cm⁻² s⁻¹
- 4000 fb⁻¹ in about 10 years ten times the luminosity reach of first 10 years of LHC operation

Around 300 fb⁻¹ the present Inner Triplet magnets reach the end of their useful life (due to radiation damage) and must be replaced.

HL-LHC Plan



Tile Calorimeter Upgrade Program

- Advanced physics goals and LHC upgrade plans create new challenges for detectors
 - LHC upgrade program aims at 5-10 fold luminosity increase → more radiation → better radiation tolerance required
 - Ageing electronics \rightarrow originally planned for 10 years of operation
 - Obsolete components \rightarrow impossible to maintain
 - Higher event rates require more efficient trigger algorithms
- A multi-phase upgrade program has been conceived: Phase-0, Phase-I and Phase-II
- The major Tile Calorimeter mechanics and optics will stay, together with associated PMTs
- Front-end and back-end electronics, calibration systems, will undergo major upgrades in Phase-II
 - Complete redesign for font-end and back-end electronics
 - New electronics drawer mechanics
 - Fully digital trigger with higher selectivity and finer granularity
 - Demonstrator project to discover and solve issues as early as possible

TDR

- Technical Design Report
 - Submitted to ATLAS Sep-2017
 - LHCC reviewed Nov-2017
 - CB approved Feb-2018
 - o RB approval Mar-2018



ATL-COM-TILECAL-2018-003 2nd February 2018



ATLAS Tile Calorimeter Phase-II Upgrade Technical Design Report

The ATLAS Collaboration

This Technical Design Report describes the project to upgrade the ATLAS Tile Calorimeter for the operation at the High Luminosity LHC. The High Luminosity LHC is planned to begin operation in 2026 and to deliver more than ten times the integrated luminosity (up to 4000 fb^{-1}) of the LHC Runs 1-3 combined. To achieve this integrated luminosity in a reasonable amount of time, an instantaneous luminosity of up to 7.5×10^{34} cm⁻²s⁻¹ is required, corresponding to up to 200 simultaneous pp interactions per bunch crossing. The large luminosity offers the opportunity for a wealth of physics measurements but presents significant challenges to the detector as well as to the trigger and data acquisition systems in the form of increased trigger rates and detector occupancy. This document summarises the requirements and motivations for the Tile Calorimeter upgrade and gives a detailed technical description of the different components. It describes the beam tests with the prototypes in recent years and the plans for the assembly, quality assurance and the integration of the final system. The document also presents the key aspects of project management with an overview of the organisation, the schedule and the cost.



Technical Design Report

Upgrade Performance



- TileCal contributes to the performance of Jets, Electron/photon, Muon and Tau
- Provides information for the calorimeter trigger
- Measurements and searches in SM/Top/Higgs/ Exotics/SUSY groups depend on the TileCal performance
- Challenges in pile-up noise
- Very stable jet response and resolution as a function of pile-up
- Jet angular resolution is very similar to that in Run-2
- Slightly worse jet energy resolution compared to that in Run-2



- Long Lived Particles (LLP)
 - Neutral LLP decays in TileCal -> displaced jet
 - Isolated and narrow energy deposits in TileCal
 - Hardware trigger with greater granularity
- Z' decay to ttbar
 - ttbar resonance search as a benchmark for a ~TeV range new particle searches : phasespace + statistics
 - Expect to observe (or exclude) the resonances with mass up to 4 TeV

Radiation Hardness



- Tile Calorimeter read-out electronics housed at the outer radius of the calorimeter, shielded by the calorimeter body
- Radiation dose requirements are not as critical as in other ATLAS sub-detectors, but...
- HL-LHC will deliver x10 more dose to the electronics
- All electronics require certification with appropriate safety factors (up to 30)

Mini Drawers

- PMTs and on-detector electronics are housed in "drawers"
- Old super-drawer design is heavy and difficult to maintain
- New design have 4 minidrawers
- Robust mechanical links
- New cooling system
- Special installation tooling
- Special design of mini-mini drawers for extended barrels to save on electronics



New Readout Architecture



- All digital data is transmitted off-detector at 40 MHz
- The data is pipelined and processed in the offdetector pre-processor boards (TilePPrs)
- Simpler on-detector electronics
- Flexibility of the off-detector data processing for the trigger
- Redundancy and reliability

HV dividers

- Measurable deviations from linearity of the PMT response are expected for anode currents > 5 μ A
- At high current the HV distribution between dynodes changes, thus changing the PMT gain
- Present Passive dividers are linear (2%) for currents $< 5 \,\mu A$
- Clermont-Ferrand developed an active divider for TileCal PMTs with linearity robust to the increased currents
- New active dividers were installed during LS1 shutdown (2013-2014) in gap/crack cells





Front-End Board (FEB)

- 3 FEB options
- Discrete
 - Optimised 3in1
- ASIC
 - o QIE
 - o FATALIC
- Prototypes of all FEB options were tested in labs and test beams
- 3in1 option was selected as a baseline





3in1:

- Improved linearity and rad. tolerance
- 2 gains (high and low)
- Charge injection calibration

QIE: -"Current splitter" with gate integrator - No pulse shaping, deadtimeless digitization at 40 MHz - Pipelined operation, 18-bit dynamic range



FATALIC: - 3-gain PMT signal analog processing - 3 embedded 12-bit ADCs (one per gain) - Auto-gain selection (Medium and {High or Low}) - 12-bit output bus (data multiplexing of 2 gains)

Main Board (MB)



- Connects FEBs to DB
- ADCs in case of 3in1, otherwise very simple
- Split into two halves for redundancy
- Each cell read-out by two PMTs, one on each side of the mainboard
- Samples are transferred serially to the daughterboard at 600 MHz
- Commands are sent in parallel to 2 control FPGAs on each side



- Provides communication with back-end electronics
 - **Redundant** system on a single PCB, 14 layers
 - Two Kintex UltraScale+ FPGAs and four SFP+ Modulators
 - Two GBTx chips
 - Firmware can be uploaded through the optical link
 - TTC and data connection with PPR

LV Power Distribution



Finger LV Power Supply (fLVPS)

- Fits the same box, revision of the power distribution scheme
- Unique +10V supply, other voltages are derived in situ using point of load (POL) regulators
- Increased redundancy
- Used at test beam





HV Power Distribution

Internal (HV-opto)

- Existing HV cable
- Internal regulation
- Subject to SEUs

Remote (HV-remote) Baseline

- New thick cables
- Remote regulation
- No rad. requirements





PPR

F. Carrio



- Interface between FE/DAQ/Trigger
- ATCA blade with CPMs
- Need 32 PPRs in total
- 4x channel prototype successfully tested
- Full-size design in progress
- TDAQi RTM to transfer the data to trigger and readout

Calibration Systems



- All calibration systems will continue to be present in the upgraded electronics
- Charge Injection for ADC calibration
- Laser for PMT gain calibration and monitoring
- Min.Bias for luminosity, pile-up and cell response monitoring
- Cs137 for absolute calibration and reference

Hybrid Demonstrator



- To fully test new electronics in real conditions
- Compatible with existing analog L1 Calorimeter trigger
- Used at test beam for 3in1 FEB option
- Ideally to be installed in one of the next shutdowns

Test Beams



- Study performance of different front-end options (3IN1, QIE, FATALIC) and HV options
- Electron, hadron and muon beams, charge injection and cesium calibration
- Studies at 350 GeV for GEANT4 shower development
- Allow new TileCal colleagues to touch detector and DAQ





New LS3 schedule (still in work) G. Usai

			2007 - 2007 - 2008 - 20
Opening Forward region	1 wk M	fon 11/12/23	
Auons Forward	120 days M	ton 08/01/24	
EOL-C	12 days M	fon 08/01/24	
BW-C MDT	30 days W	Ved 24/01/24	
BW-C TGC3	44 days F	Fri 08/03/24	
BW-C TGC1	32 days T	'hu 09/05/24	
EOS-C	12 days T	ue 07/05/24	
BW-A TGC3	44 days M	fon 08/01/24	
EOL-A	12 days F	Fri 08/03/24	
BW-A MDT	30 days T	ue 26/03/24	
BW-A TGC1	32 days T	ue 07/05/24	
EOS-A	12 days T	thu 23/05/24	
Inening step 7	1 wk M	Ion 24/06/24	
AS removal	20 days M	ton 01/07/24	
TAS removal - Side C	Z wks M	App 01/07/24	
This removal - Jule C	2 who in	tee 15/07/24	
TAS removal - Side A	2 wks N	non 15/07/24	
pening completion	a with a market and a market a	ton 15/07/24	
decommissioning	301 days M	ton 08/01/24	
services removal at PP2	7 mons M	non 08/01/24	
services removal from Detector to PP2	10 wks M	ton 09/09/24	
Pixel/IBL removal	11 wks M	fon 09/09/24	
Services at PP1 (A & C)	1 mon M	Non 25/11/24	
End cap C extraction	7 days W	Ved 08/01/25	
Services Barrel side C	2 wks F	Fri 17/01/25	
End cap A extraction	7 days	Fri 24/01/25	
Services + Barrel extraction (side A)	3 wks T	ue 04/02/25	
Cryostat preparation	3 wks T	ue 25/02/25	
rk.	198 days T	ue 12/08/25	
Lowering & insertion	1 mon T	ue 12/08/25	
Services & commissioning	8 mons T	'hu 11/09/25	
Auons Barrel	625 days M	ton 08/01/24	
BIS side A - extraction	26 days M	fon 09/09/24	
BIS side C - extraction	26 days F	Fri 24/01/25	
BIL MDT electronics	19 mons T	ue 15/10/24	
Barrel new RPC	15 mons M	fon 10/03/25	DIL & RF
New BIS side A - installation 1-3	14 days T	ue 12/08/25	
New BIS side A - installation 4-6	14 days	Fri 12/12/25	
New BIS side C - installation 1-3	14 days M	App 27/10/25	
New BIS side C - installation 4-6	14 days T	bu 15/01/26	
BM and BO MDT electronics	28 mons h	dop 08/01/24	
inuid Arron	304 days M	lon 10/03/25	
Barrel & electronics	10 with T	up 03/06/25	
Barral C electronics	13 min 1	tee 10/03/35	
Barrer Celectronics	12 WIG N	10/03/25	
Frechour Liming detector - Side C	a mon T	Fel 12/12/25	
End Cap C electronics	9 WKS	rn 12/12/25	
Precision Timing detector - Side A	1 mon M	Non 02/06/25	
End Cap A electronics	9 wks T	ue 12/08/25	
LAr commissioning	12 wks	Fri 27/02/26	
ile Cal	482 days W	fed 31/07/24	
LBA module extraction	12 days V	Wed 31/07/24	
EBA module extraction	11 days	Fri 16/08/24	
LBC module extraction	3 wks N	Mon 05/08/24	
EBC module extraction	10 days N	Mon 26/08/24	
LBA	10 wks T	ue 25/03/25	
LBC	10 wks T	ue 03/06/25	
EBA	10 wks T	ue 14/10/25	
EBC	10 wks	Fri 27/02/26	
Tile commissioning	8 wks	Fri 08/05/26	
losing Barrel - Side C	R with a	Fri 03/07/26	
osing Barrel - Side A	8 wks	Fri 03/07/26	
Varig barret - side A	and and and	1 38/08/26	
As replacement	40 days F	PT 28/08/26	
TAXS Installation - Side C	4 wks	Fn 28/08/26	
TAX5 installation - Side A	4 wks	en 25/09/26	Detector closing ——/
eam pipe bakeout	3 wks F	Fri 23/10/26	
Closing Forward - side C	2 wks F	Fri 13/11/26	

• LHC Days in Belarus 2018

CERN

ATLAS opening (ALARA)

14 TeV pp ATLAS Standard Opening Res. Dose Rate | 2010-2023, 297 fb⁻¹ total



New installation tools



- A set of new installation tools was developed for new mini-drawer mechanics concept
- Successfully tested and validated in the labs, test beam and real detector



Life Days in Delaros 2016

Past experience (LS1)









EB module extraction from rear side (if no enough access to the Finger). Special 3m basket, additional platform , more complicate => much more time.



- All 256 Super-drawers were extracted, refurbished and put back during LS1
- Great teamwork

LHC Days in Belarus 2018

Optics Robustness



- PMT response degrades with integrated anode current
- PMTs in the lab have integrated up to 270C of charge, we expect 600C for 4000 *fb*⁻¹ at HL-LHC.
- Extrapolated average signal loss at 600C: -36%±6%
- Decided to replace the most affected PMTs (~800 out of 10000) with more recent and stable version R11187SEL

- Scintillator and fiber optical qualities degrade with integrated dose
- Current estimation is <10% for the inner layer
- Even in case of dramatic loss of 50% do not expect significant performance degradation



Number of Tile PMTs per bin of nominal response loss (%)

Optics Robustness



- Tile scintillators custom made from PS (PSM-115, BASF-165H)
 and PTP+POPOP more than 20 years ago
- Radiation hardness tests showed acceptable degradation for 10 years of original LHC
- LHCb uses almost the same scintillator material but under harsher conditions
- Gap/crack (E) scintillators are made from different materials

Other studies

Gap/crack scintillators



• O. Solovyanov / Tile week



- 512 scintillation detectors
- Cells E1-E2(gap), E3-E4(crack)
- Light collected by WLS fibres and then transported by clear fibres
- Read out by Tile PMTs

Gap/crack scintillators





BAL vs. irradiation dose. D.R.=0,02 Mrad/h. After recovery period 270 days. Samples 9x20x200 mm



- Tile gap/crack scintillation counters play an important role in e/gamma and Jet/Etmiss performance
- Counters can be replaced after irradiation damage
- New, more segmented geometry and increased radial coverage up to $\eta \sim 1.75$ improve physics performance
- The new, more radiation hard scintillation material and detector geometry is being studied, including more pile-up robust reconstruction algorithms
- Few counters were replaced in LS1 with new scintillator and new geometry
- Green plastic and crystal composite scintillators are also being studied



• LHC Days in Belarus 2018

MAPMT idea

- Tile granularity shows limitations on high p_T boosted jets, jet substructure, long lived particles (NNLP)
- Can not and do not plan to change the calorimeter in Phase 2, however...
- Individual fibres bring information from different cell regions, in η and R
- Map fibres onto multi-anode PMT
- Configurable analogue sum of 8x8 channels of MAPMT (used in ALFA and LHCB) to split fibres into 2-4 areas
- Identify and calibrate with Cs scan
- Difficult!!! Possible???
- Evaluate in parallel: physics gain, impact on electronics layout and bandwidth
- Improved granularity scenarios:

 Inner A barrel layer η granularity: by factor 2-4, Δη= 0.1 → 0.05-0.025
 Separate B and C cells in R: A=1.5 λ; B~1.9λ;C~2.3 λ;D=1.9 λ
- IDR chapter with lots of material
- Not mature enough for TDR, continue with R&D to be ready for future upgrades (if any)



B/C separation

MAPMT calibration A. Bisulco





MA

MA-

MA

MA



• LHC Days in Belarus 2018

27.02.2018 • 50

MAPMT coupling Light guides

A. Bisulco





MA-PMT L = Focal Length Objective Lens + Focal Length Image Lens

Magnification factor MF = FL_{objective} / |FL_{image} |

Telescope

 $\begin{array}{rrrr} MF = 2.0 & ==> & FL_{objective} & = 50 \mbox{ mm, } FL_{image} = -25 \mbox{ mm, } L = 25 \mbox{ mm} \\ MF = 2.4 & ==> & FL_{objective} & = 60 \mbox{ mm, } FL_{image} = -25 \mbox{ mm, } L = 35 \mbox{ mm} \\ \end{array}$

Air





Fokon

• LHC Days in Belarus 2018

27.02.2018 • 51

MAPMT readout



- Main problem 64x number of channels
- Need to sum-up sub-cells
- Two concepts analogue and digital sum

Future Accelerators

Compact Linear Collider (CLIC)

Linear e^+e^- collider \sqrt{s} up to 3 TeV

100 MV/m accelerating gradient needed for compact (~50 km) machine

→ based on normal-conducting accelerating structures and a two-beam acceleration scheme



Most recent operating scenario: start at \sqrt{s} =380 GeV for H and top physics



Parameter	Unit	380 GeV	3 TeV
Centre-of-mass energy	TeV	0.38	3
Total luminosity	10 ³⁴ cm ⁻² s ⁻¹	1.5	5.9
Luminosity above 99% of \sqrt{s}	10 ³⁴ cm ⁻² s ⁻¹	0.9	2.0
Repetition frequency	Hz	50	50
Number of bunches per train		352	312
Bunch separation	ns	0.5	0.5
Acceleration gradient	MV/m	72 7.02.2018	³ 100

• LHC Days in Belarus 2018

Future Circular Collider (FCC)

International FCC collaboration (CERN as host lab) to study:

pp-collider (*FCC-hh*)
 → main emphasis - defining infrastructure requirements

~16 T \Rightarrow 100 TeV *pp* in 100 km

- **80-100 km tunnel infrastructure** in Geneva area, site specific
- e⁺e⁻ collider (FCC-ee), as potential first step
- *p-e* (*FCC-he*) **option**, integration one IP, FCC-hh & ERL
- **HE-LHC** with *FCC-hh* technology
- CDR for European Strategy Update 2018

 LHC Days in Belarus 2018



FCC-hh

C. Neubüser



- HL-LHC operation until 2035
 - ~ 30 years from design to data taking
 - Development of FCC collider and detector needed NOW
 - To be ready after HL-LHC ~2036

FCC-hh detector

baseline FCC week Berlin May 2017

total length \sim 47 m, height \sim 18 m

Magnet	Tracker	
3 solenoids not fully shielded 4 T, 2.5 and 5 m radius	1.5 m rac σp _T /p _T (10 TeV)	





C. Neubüser

FCC-hh hadronic calorimeter – Scintillator-Steel I

1. Current baseline for FCC-hh

ATLAS type, Scintillator tile - Steel

changes for FCC-hh:

- 4 times higher granularity $\Delta \phi \times \Delta \eta = 0.025 \times 0.025$
- 10 instead of 3 longitudinal layers
- Steel -> stainless Steel absorber (Calos in magnetic field)
- SiPM readout -> faster, less noise, less space





Resolution for single pions in 11 λ HCAL: $\sigma E/E = 43 \%/\sqrt{E} \oplus 2.7\%$

Good containment achievable with $\sim 11\lambda$ calorimeter system (ECAL+HCAL) at $\eta = 0$

Hadronic Calorimeter II



- 120 modules in phi , 6m long in Z is ok => Df =0.05, 2 times better than ATLAS Rmin=3.5m. Rout =5.8m. Need 20cm for cables before solenoid
- Depth Outer Supports=20cm (15cm girder+5cm Xbars);~1.5 shorter than ATLAS!
- 20 tons each module of 6 m long in Z + 0.7 tons Xbars per module
- Total FCC TileCal barrel weight of 18m long = 7500 tons (3x2500)

A. Henriques, N. Topilin

• LHC Days in Belarus 2018

Summary

- Tile Hadron Calorimeter is an important part of ATLAS detector at LHC, CERN
- High Luminosity LHC upgrades poses significant challenges and requires a full redesign and replacement of front-end and back-end electronics
- Prototypes of several options are available and are being tested in the labs and at test beam
- Submitted the ATLAS TileCal Phase-II Upgrade TDR
- Future experiments at future accelerators might benefit from TileCal-like calorimeters