

ASTERIX: Development of TIG-Welded Four-Quadrant X-Band RF Accelerating Structures at INFN.

Luigi Faillace

INFN – LNF, Frascati (Rome), Italy



Project Overview

The main goal of ASTERIX is the design, fabrication and high-power RF testing of a **practical meter-long, four-quadrant, “open-type” X-band accelerating structure** made of hard copper, joined and vacuum-sealed by TIG welding — a braze-free technique — targeting gradients above 100 MV/m.

- high **accelerating gradients (>100 MV/m)**
- composed of **four-quadrants** (“open-type”)
- made out **hard copper**
- joined and vacuum sealed by using **TIG welding** (“braze-free” technique)


Funded by Scientific Committee 5 of INFN

Collaboration

LNF coordination · mechanical & RF design

LNS RF couplers · multiphysics simulation

Roma1 wakefield & HOM characterisation



90 cm, four-quadrant, TIG-welded “open-type” structure with integrated mode-launcher, cooling channels and tuners.


ASTERIX (Accelerating **S**tructures made of multiple sector**S** In **X**-Band)

PI: Luigi Faillace INFN-LNF

3 years (2025-2027)

Total budget = 400 kEuros

ASTERIX INFN- team



LNF	FTE	LNS	FTE	Roma1	FTE
L. Faillace (Resp. Naz.)	0.3	G. Torrisi (RL)	0.1	L. Ficcadenti (RL)	0.3
D. Alesini	0.2	D. Mascali	0.05	M. Petrarca	0.2
M. Bellaveglia	0.05	G. Mauro	0.1	M. Migliorati	0.2
S. Bini	0.2	G. Sorbello	0.2	G. Silvi	0.2
F. Cardelli	0.3	T. Isernia	0.3	L. Palumbo	0.4
M. Carillo	0.2	R. Palmeri	0.3		
E. Chiadroni	0.2	A. Locatelli	0.1		
A. Falone	0.2	C. De Angelis	0.1		
A. Gallo	0.15	L. Vincetti	0.1		
A. Giribono	0.2				
A. Liedl	0.1				
L. Piersanti	0.1				
S. Pioli	0.2				
B. Spataro	0				
C. Vaccarezza	0.2				
Tot./Unit	2.6		1.35		1.3


This work is made possible by the efforts :

INFN

Laboratori di Frascati, Roma1 (Sapienza University) and
Laboratori del Sud (Catania)

SLAC(USA)

KEK (JAPAN)



External Collaborators: V. Dolgashev (SLAC), Tetsuo Abe (KEK)

USTC (CHINA)

University of Science and Technology of China: Yelong Wei, PhD
student Zhicheng Huang in Frascati.




History

- **MOU between SLAC and INFN-LNF** within the world-wide collaboration on studies of RF breakdown physics in RF accelerating structures:
from **X-band** (11-12 GHz) to other frequencies (S, C, Ka, W) .


- **DEMETRA (2016-18)**

- **ARYA (2020-23)**

Funded by
CSN5 (V. Bonvicini)



Courtesy of B. Spataro





- **MICRON (2022-24)**

Ka-band structures
made of four quadrants


Resp. Loc. L. Faillace - LNF

Funded by CSN5 (A. Quaranta)

Luigi Faillace



RF power
Coupler:
4-port Mode Launcher




ASTERIX


**Accelerating Structures
made of multiple sectors
In X-Band**

State-of-the-art

1. “Single-cell” cavities (open and closed; disk-type and multi-sector)



2. TW multi-cell structures (open and closed; disk-type and multi-sector)
3. Open-type multi-sector cavities, typically of small lengths (20-30 cm).



KEK (Tetsuo Abe) 2023

- X-band
- 4 quadrants
- EBW welding
- To be High-power tested.

(T. Abe)






Figure 3: A quadrant fabricated with ultraprecision milling.





CERN 2007 (Dobert, Grudiev, Wuensch et al)

- X-band
- 4 quadrants
- Clamped, high T-treated
- High-power Tested:


→ Gradient: 80 MV/m with 40 ns pulse length.




Dolgashev VA, Faillace L, Spataro B, Tantawi S, Bonifazi R. High-gradient rf tests of welded X-band accelerating cavities. Physical Review Accelerators and Beams. 2021 Aug 10;24(8):081002.




Full TW multi-cell X-band structure



Full TW multi-cell X-band structure







7 Milestones




6 Deliverables

Luigi Faillace

ASTERIX cell geometry for single-bunch mode



Rounding: 0.5mm



Cell Optimization

Optimization Target:

Low peak electric field **E_p** , magnetic field **H_p** , modified Poynting vector **Sc**

High shunt impedance **R_{sh}** and **Q**

Elliptical ratio $\rightarrow E_p, Sc$

Rounding top $\rightarrow H_p$

Iris radius fixed at $a = 3.5\text{mm}$

Conventional disk-loaded structure:


$E_p/E_{acc} \approx 2.1$

$H_p/E_{acc} \approx 2.6 \text{ mA/V}$

$Sc/E_{acc}^2 \approx 0.6 \text{ mA/V}$



$Q = 6800\text{-}7500$ (different rounding)

$R_{sh} = 105\text{M}\Omega/\text{m}$



The value will be shown later

Modified Poynting Vector and Peak E field




t=2ae=2mm, **gap = 0.5mm**

Optimal value: Sc/Eacc² = 0.694

Ep = 2.26

Desired point: be = 1.7mm

Luigi Faillace




t=2ae=2mm, **gap = 1mm**

Optimal value: Sc/Eacc² = 0.827

Ep = 2.44

Desired point: be = 1.5-1.6mm

Advanced Accelerator Concepts 2026, Jul 26 – 31



t=2ae=2mm, **gap = 1.5mm**


Optimal value: Sc/Eacc² = 0.963

Ep = 2.60

Desired point: be = 1.6mm


Luskin Conference Center, UCLA

Hp, Rsh and Q for gap=1mm




$t=2\text{mm}$, **gap = 1mm**

No significant influence



$t=2\text{mm}$, **gap = 1mm**

Optimal Q :7000




$t=2\text{mm}$, **gap = 1mm**

Optimal impedance: 98.21 $M\Omega/m$

Hp is hard to be reduced !!

RF design of the full-scale structure



Top: full 1-metre-long, four-quadrant structure model. Bottom: on-axis electric-field profile.

Parameter	Value
Frequency	11.994 GHz
Accelerating gradient	100 MV/m
Input power	77 MW
Operating mode	$2\pi/3$
Number of cells	120
Full structure length	1 m
Quality factor	6931
Shunt impedance	97.3 MΩ/m
Peak surface field, Ep	245 MV/m

RF–thermal–mechanical multiphysics


Closing the loop between RF losses, cooling, deformation and RF detuning

**1 RF baseline
field profile
phase advance**


**2 Thermal
wall losses
temperature map**

**3 Mechanical
thermal expansion
deformation**

**4 RF feedback
S-parameters
field profile**



**CST/COMSOL cross-check: temperature
distributions agree within about 1 °C.**




Frequency and field profile/Phase show negligible
variation due to temperature gradient distribution
along structure

Multipacting, wakefields and HOM studies


Risk reduction before high-power operation

Multipacting analysis




- gradient scan on full quarter-cell model
- gap-size study in internal technical report
- electron population decays in simulations (no MP)
- no critical multipactor observed in investigated range 0.1 mm – 1mm gap (the average SEY remains below unity across the explored gradient range, and the mean collision energy stays below the SEY-unity threshold)


Wakefields / HOM optimization



- single- and multi-bunch operation considered
- HOM mitigation compatible with open-sector concept



- single-bunch case, a Gaussian beam with 1 mm rms bunch length and 200 pC of charge → 1keV energy spread



Mechanical design & prototype fabrication

During the first project year, LNF completed the mechanical drawings and engineering of the full-scale structure (without RF couplers), fabricated to validate:


- TIG-welding process
- Structure straightness & quadrant alignment
- Vacuum performance

Machining — complete


Machine: Doosan DNM 750L CNC

Roughness: $R_a < 1 \text{ } \mu\text{m}$

All four quadrants machined on a single CNC capable of hosting the full-length parts.




Final CAD model — tuning pins, alignment pins, welding teeth, central pumping port and secondary vacuum chambers.



One quadrant on the inspection table (left); close-up showing individual machined cells (right).

Joining and welding

The quadrants were joined by **TIG welding**, with inert gas flushed during the process to protect the weld and preserve the internal vacuum surfaces — the “brazo-free” approach central to ASTERIX.



Luigi Faillace



Left: ASTERIX prototype being TIG welded. Right: TIG-welded prototype on the CMM table for mechanical characterization.

Qualification status

A comparison of the dimensional measurements acquired before and after the welding process indicates only minor deviations at the inspected locations:



→ straightness **max error 20 μm , over 1 m.**

The observed dimensional variations are minimal and within the expected process capability

→ the welding operation preserved the dimensional integrity of the component and was successfully completed without introducing significant deformation.

Result: Positive

Mechanical and vacuum tests on the welded prototype were performed and produced a positive outcome.



Vacuum Leak Check



Conclusions and Future Work

- Two small-scale prototypes, in single-bunch geometry, to be LOW and HIGH power tested in 2026.
- Low RF power measurements are performed at the INFN LATINO Lab.
- **Full length structure (single-bunch mode) to be machined and high RF powered tested at TEX Facility in Frascati by the end of 2027.**

