

# Status of the Superfluid Helium UCN source at TRIUMF


Ryohei Matsumiya (RCNP, Osaka U → TRIUMF)  
& The TRIUMF Japanese-Canadian UCN Collaboration  
CAP2017

June 1, 2017, Queen's University, Kingston, ON

# Index


- Super-thermal UCN Production
- The vertical UCN source
- Installation & Cooling tests
- Summary & Schedule for UCN production

# Super-thermal UCN Production



- Produce fast neutrons by proton-induced spallation  
~ a few MeV
- Moderate (thermalize) neutrons in 300K and 20K D<sub>2</sub>O  
~ a few meV
- Cold neutrons are down-scattered to near zero energy by phonon scattering in superfluid helium (He-II)  
< 300 neV

# Super-thermal UCN Production



UCN Production rate in He-II

$$P = \int dE_{ucn} \int dE_{in}$$

$$N_{4\text{He}} \frac{d\sigma(E_{in} \rightarrow E_{ucn})}{d\omega} \frac{d\Phi_n(E_i)}{dE}$$

He-II  
density

cross  
section

cold n flux

$$\frac{d\sigma}{d\omega} = 4\pi b_{coh}^2 \frac{k_f}{k_i} S(Q, \omega)$$

scattering length


wave number of incident n

Scattering function


wave number of scattered n


M. R. Gibbs et al.

J. Low. Temp. Phys. 120 (2000) 55.




The Vertical UCN Source  
KEK-RCNP-TRIUMF






The Vertical UCN Source  
KEK-RCNP-TRIUMF









The Vertical UCN Source  
KEK-RCNP-TRIUMF

# UCN Source Development in RCNP (2002~2011)



## Best record (2011)

- p-beam: 400W (1 $\mu$ A $\times$ 400MeV)
- UCN density: 26 UCN/cm<sup>3</sup> ( $E_c = 90\text{neV}$ )
- UCN storage time:  $\tau = 81 \text{ sec}$

Y. Masuda et al., Phys. Rev. Lett. 108 (2012) 134801.


- 2002 First UCN production
- 2011 Development finished
- 2016
  - Shipping from RCNP to TRIUMF
  - Safety upgrade of the cryostat
- 2017
  - Cooling tests
  - Installation on beam line 1U

# Cooling tests

- 2017 February - First cooling test
  - Cooling the cryostat with only GM refrigerator
  - Liquid helium was not used.
  - Confirmed the GM refrigerator worked. The cryostat was cooled down to 12K.
  - Pre-cooling the cryostat had no problem.

UCN cryostat installation on beam line 1U

- 2017 April - Full cooling test
  - After pre-cooling by GM refrigerator, we put liquid helium into the cryostat.
  - Succeeded in condensing He-II.
  - The He-II temperature was 0.92K.




1st cooling test in Meson hall  
(not on the beam line)

# The UCN Cryostat Installation onto Beamline 1U



# The UCN Cryostat Installation onto Beamline 1U



UCN cryostat


Liquid helium  
auto fill system

Helium-3  
gas handling panel

DAQ etc.


# The UCN Cryo

# into Beamline 1U




UCN cryostat

$^3\text{He}$  pump



Liquid helium auto fill system



$^3\text{He}$  gas handling panel





DAQ etc.

Compressors

13/04/2017 12:48  
Turned ON GM compressors  
Pre-cooling started

# Temperature log of the full cooling test








# Movie: Work in Meson hall

Jan 3 ~ May 1, 2017




# Summary & Schedule for UCN production

---

- The vertical UCN source was developed in Japan, and achieved a UCN density of  $26 \text{ UCN/cm}^3$  ( $E_c = 90 \text{ neV}$ ). The UCN source was shipped to TRIUMF in 2016.
- The UCN cryostat was installed on the beam line 1U after safety modification.
- We succeeded in condensing He-II and lowering the temperature to 0.92K.
  - He-II temperature was a bit higher than RCNP (0.8K)
  - Acceptably low temperature ( $<1 \text{ K}$ ) for long UCN storage time
- Schedule for UCN production
  - June 20: Start pre-cooling & D<sub>2</sub>O cooling
  - July 21: Start liquid helium transfer, then He-II condensation
  - Aug 1: Ready for UCN production

Backup slides

# The vertical UCN source in the east hall of RCNP




# Improvement of the UCN storage time

Year	$I_p$	$\tau_s$	$T_{\text{HeII}}$	Improvement
2002	200nA	14 s	1.2K	
June 2006	1 $\mu$ A	29 s	0.9K	$^3\text{He}$ cryostat
Nov. 2006	1 $\mu$ A	34 s	0.8K	Reduce HeII film perimeter (8.5 cm $\rightarrow$ 5 cm)
July 2007	1 $\mu$ A	39 s	0.8K	Remove $^3\text{He}$ contamination
April 2008	1 $\mu$ A	47 s	0.8K	Fomblin coating
Dec. 2009	1 $\mu$ A	61s	0.8K	Alkali cleaning
Feb. 2011	1 $\mu$ A	81s	0.8K	High temperature baking (140°C)



- Decreased phonon up-scattering by lowering  $T_{\text{He-II}}$
- Removed  $^3\text{He}$  in superfluid helium by introducing isopure helium ( $^3\text{He}/^4\text{He} < 10^{-11}$ )
- Surface cleaning by alkali degreasing and high temperature baking

# Cryostat Safety Upgrade (4K reservoir & UCN guide)





Liquid helium  
4.2K, 60L max

He-II  
<1K, 8~9L




- When the insulating vacuum is broken, heat load on liquid helium becomes ~10kW.
- Liquid helium is boiled off.
- We installed burst disks to save the cryostat.



Burst disk at  
UCN guide end

# 1st cooling test (detail)




V-cryostat

Compressors


- Moved the cryostat to Meson hall (Feb 2)
- Put LN2 into 4K reservoir (Feb 3)
- Turned on compressors (Feb 6)
- Ice D<sub>2</sub>O vessel became ~20K (Feb 8)
- 1K pot, <sup>3</sup>He pot, UCN guide became ~ 77K (Feb 13)
- Cold leak test (Feb 14)
- Turned off compressors (Feb 14)

# Temperature log of the 1st cooling test






# Liquid helium consumption




Liquid Helium Level in the Stationary Dewar




# Heat load test

- 1uA p-beam: 25mW heat load by  $\gamma/\beta$ -heating
- Put heat load on the He-II volume using a heater wound around the UCN bottle.
- Heater power: 2.5mW, 12.5mW, 25mW, 75mW, 250mW, 1000mW, 4000mW
- Heating time: 10sec, 20sec, 60sec, Continuous (5minutes or more)



Heater power 1000mW, 60sec  
 $\Delta T$  (UCN double tube bottom) = 62mK  
 $\Delta T$  (UCN double tube top) = 43mK



Heater power 1000mW, Continuous  
 $\Delta T$  (UCN double tube bottom) = 280mK  
 $\Delta T$  (UCN double tube top) = 230mK  
(Had to abort test)

# Heat load test

Heater power [mW]	Heating time [s]	$\Delta T$ (UCN double tube bottom)	$\Delta T$ (UCN double tube top)
2.5 (0.1uA p-beam)	10	0	0
	20	0	0
	60	0	0
	continuous	1 mK	1 mK
12.5 (0.5uA p-beam)	10	1 mK	1 mK
	20	1 mK	1 mK
	60	2 mK	1 mK
	continuous	4 mK	4 mK
25 (1uA p-beam)	10	1 mK	1 mK
	20	-	-
	60	4 mK	3 mK
	continuous	10 mK He-II 0.93K	9 mK
75 (3uA p-beam)	10	3 mK	2 mK
	20	3 mK	3 mK
	60	10 mK	7 mK
	continuous	30 mK He-II 0.95K	20 mK
250 (10uA p-beam)	10	6 mK	3 mK
	20	11 mK	7 mK
	60	27 mK	17 mK
	continuous	72 mW He-II 1.0K	53 mK
1000 (40uA p-beam)	10	21 mK	13 mK
	20	32 mK	21 mK
	60	62 mK	43 mK
	continuous	280 mK (test aborted)	230 mK (test aborted)
4000 (160uA p-beam)	10	51 mK	35 mK

UCN storage time

$$\frac{1}{\tau} = \frac{1}{\tau_n} + B \cdot T^7$$

$$\tau_n = 880 \text{ sec}$$

T [K]	$\tau$ (B=8x10 <sup>-3</sup> )
0	880
0.5	834
0.7	557
0.8	355
0.9	202
1.0	109