

The SNO+ Scintillator Fill



Benjamin Tam (for the SNO+ Collaboration)
2022 CAP Congress
June 8, 2022



Situated 2km underground to suppress cosmogenic backgrounds


9800 photomultiplier tubes (PMTs) mounted on 8.9m radius support structure

Body: 6.0 m radius acrylic vessel (AV)

7000 tonnes of water shielding

905 tonnes of water or 780 tonnes of liquid scintillator

System of ropes to account for buoyancy differences



Three Operational Phases based on AV medium:

Phase	Medium	Physics Goals	Dates
1	Ultrapure Water	<ul style="list-style-type: none">Invisible Nucleon Decay searchSolar Neutrino MeasurementsSupernova neutrinosAxion-like particle search	Operated May 2017 – July 2019
Scintillator Fill: Replace ultrapure water with liquid scintillator			
2	Liquid Scintillator	<ul style="list-style-type: none">Solar neutrino measurementsReactor anti-neutrino measurementsGeo-neutrino measurementsSupernova neutrinos	Operation started April 2022
Tellurium Loading: Dope liquid scintillator with tellurium isotope			
3	Tellurium-loaded Liquid Scintillator	<ul style="list-style-type: none">Neutrinoless double beta decay search in $^{130}\text{Te}^*$ <p>*Primary Physics Goal</p>	Planned initial deployment 2024


Three Operational Phases based on AV medium:

4

Phase	Medium	Physics Goals	Dates
1	Ultrapure Water	<ul style="list-style-type: none">Invisible Nucleon Decay searchSolar Neutrino MeasurementsSupernova neutrinosAxion-like particle search	Operated May 2017 – July 2019
Scintillator Fill: Replace ultrapure water with liquid scintillator			
2	Liquid Scintillator	<ul style="list-style-type: none">Solar neutrino measurementsReactor anti-neutrino measurementsGeo-neutrino measurementsSupernova neutrinos	Operation started April 2022
Tellurium Loading: Dope liquid scintillator with tellurium isotope			
3	Tellurium-loaded Liquid Scintillator	<ul style="list-style-type: none">Neutrinoless double beta decay search in $^{130}\text{Te}^*$ <p>*Primary Physics Goal</p>	Planned initial deployment 2024

Liquid Scintillator

- Linear Alkylbenzene (LAB) + Diphenyloxazole (PPO)



- Developed by SNO+, successfully used in Daya Bay and RENO
- LAB more compatible with acrylic and safer than other widespread liquid scintillators


Pseudocumene (PC) (Borexino, KamLAND)

Phenyl-o-xylene (PXE) (Double CHOOZ)

- PPO acts as a fluor emitting in the ~420nm range
- >50x higher light yield than water

Scintillator Purity

Simulated SNO+ Backgrounds in $0\nu\beta\beta$ ROI



Chief experimental challenge for all physics goals

Controlled by ensuring extreme scintillator purity during the scintillator fill

Purpose-built scintillator purification plant build underground

Purification Strategy

Stage 1: Bulk Fill of the AV

A. High quality LAB shipments arrive in 20T tanker trucks



B. Shipped underground in passivated 2T steel railcars while under N₂ cover gas



C. Purified in scintillator purification plant **primary** processes



D. Purified LAB sent to the top of the detector



Water removed from the bottom of the detector

Purification Strategy

Stage 1: Bulk Fill of the AV

A. High quality LAB shipments arrive in 20T tanker trucks




B. Shipped underground in passivated 2T steel railcars while under N₂ cover gas



C. Purified in scintillator purification plant **primary** processes




D. Purified LAB sent to the top of the detector



E. Purified LAB diverted




F. "Neutrino-grade" high quality PPO added to LAB



G. Purified in scintillator purification plant **secondary** processes

H. Purified PPO added


Water removed from the bottom of the detector



Purification Strategy

Stage 2: Recirculation

A. Continuously **recirculated** in scintillator plant to remove water



Purification Strategy

Stage 2: Recirculation

A. Continuously **recirculated** to remove water in scintillator plant




B. Scintillator diverted



C. "Neutrino-grade" high quality PPO added to LAB



D. Purified in scintillator purification plant **secondary** processes




Scintillator Purification Plant

Primary Processes (For LAB)

- Multistage distillation
Removes lower volatility impurities including heavy metals and oxidized organics
- N₂ and steam stripping
Removes dissolved gases and volatile liquids including water
Used during **recirculation** to remove residual water

Secondary Processes (For PPO)

- N₂ stripping
Removes dissolved gases and volatile liquids
- Water extractions
Removes ionic impurities
- High temperature “flash” distillation
Removes heavy metals and oxidized organics



Scintillator Quality Assurance

Scintillator tested and assessed for quality hourly during all purification plant operation and detector filling

- **Nephelometry:** Assesses solid particulate contamination
- **Densimetry:** Assesses liquid and dissolved contaminants
- **UV-Vis Spectroscopy:** Assesses optical clarity (proxy for radiopurity), verified PPO concentration



Further tests also regularly performed

- **Infrared Spectroscopy:** Accesses absorption for contaminants at wavelengths beyond UV-Vis
- **Neutron Activation:** Additional elemental concentration analysis
- **Light yield:** Verified through a 6L 4-PMT detector
- **Karl-Fischer Titration:** Measures water concentration



Quality assurance team underground 24 hours/day...

Scintillator Fill Complete!

Completed April 29, 2022

- 792.4 tonnes LAB purified and added
- 2.01 tonnes PPO purified and added
- 4376.9 tonnes recirculated
- 4925 scintillator samples tested through the quality campaign

Final SNO+ Scintillator


LAB + 2.2 g/L PPO



"The Last Sample"


How did we do?

UV-Vis Absorption Spectrum




UV-Vis Absorption Spectrum

Optical clarity is superior to the best possible manufacturer standard at all wavelengths above PPO absorption!



Light Yield

Measured Light yield aligned with existing measurements and models!



Other Measurements

Density

0.857 ± 0.001 @ 20°C
Follows expected linear
relationship at all near-
operational temperatures!


Index of refraction

1.483 ± 0.001 @ 20°C

Water Content

< 5ppm

(method detection limit of Karl
Fischer titration)





SNO+ Scintillator Phase officially underway!
New physics results coming soon...



August 10, 2019



University of Alberta
 U.C. Berkeley
 LBNL
 Boston University
 Brookhaven
 University of Chicago
 U.C. Davis
 T.U. Dresden
 Lancaster University
 Laurentian University
 LIP Lisbon



LIP Coimbra
 Kings College London
 University of Liverpool
 UNAM
 University of Oxford
 University of Pennsylvania
 Queen's University
 Queen Mary University
 SNOLAB
 University of Sussex
 TRIUMF





Backup Slides

Deck Clean Room

Acrylic Vessel (AV)


PMT Support Structure (PSUP)

Cavity



Contaminant Type	Distillation 220°C @40 Torr	N2/Steam Stripping 100°C	Water Extraction
Heavy Metals (radioactive)	Bi, K, Pb, Po, Ra, Th		U, Th, Ra, K, Pb
Dissolved Gases (radioactive)		Ar, Kr, O ₂ , Rn	
Oxidised Organics (Optical clarity)	Carboxyl groups, 1,4-benzoquinone		
Volatile Liquids (Optical clarity)		Residual water	

Plant operations during the bulk fill



Plant Operations during recirculation

