

The LHC and preparations for HL-LHC

Mike Lamont for the LHC team
Annual meeting of the Institute of Physics
Particle Accelerators and Beams Group
7th April 2017

*

LHC Status




2.1%

☀ *Running...*

Exit Run 1(2010 – 2012)

- Foundations well proven at 4 TeV
 - Magnets, vacuum, cryogenics, RF, powering, instrumentation, collimation, beam dumps etc.
- Huge amount of experience gained
 - Operations, optics, collimation...
- Healthy respect for machine protection

**Technology: beautiful,
when well done!**



2013 - 2015

28th October
 Physics with record number of bunches
 Peak luminosity $5 \times 10^{33} \text{ cm}^{-2}\text{s}^{-1}$

April '13 to Sep. '14



3rd June
 First Stable Beams




Number of Bunches Beam 1
2244

Number of Bunches Beam 2
2244



13-14 | Aug 14-Apr 15 | 2015




Dipole training campaign




10th April
 Beam at 6.5 TeV

Struggle



IONS



Pb-Pb at $v_{sNN} = 5.02 \text{ TeV}$

LHC 2016


Choose a relatively bold set of operational parameters based on past experience

- Energy: 6.5 TeV
- 25 ns beam - nominal bunch population ($\sim 1.2e11$)
- Low emittance from injectors – variations possible
- Squeeze harder in ATLAS and CMS
 - **beta* = 40 cm**
 - cf. 80 cm in 2015
 - cf. 55 cm design

$$\mathcal{L} \propto \frac{1}{\beta^*}$$

Squeeze in ATLAS/CMS

- Lower beta* implies larger beams in the triplet magnets
- Larger beams implies a larger crossing angle
- Aperture concerns dictate caution – experience counts



2016 - overcome a few problems

WEASEL



PS MAIN POWER SUPPLY




SPS BEAM DUMP

- Limited to 96 bunches per injection in 2016
- 2220 bunches per beam cf. 2750



Luminosity lifetime




Excellent luminosity lifetime – main component - proton loss to inelastic collisions in ATLAS, CMS and LHCb

An extra boost from the injectors

The LHC performance fully relies on the **performance of its injector complex**


- By itself **one of the largest accelerator facilities in the world** with its own diverse and, for many aspects, unique physics program



An extra boost from the injectors


The LHC performance fully relies on the p

- By itself **one of the largest accelerators** in the world, the LHC is a complex system of diverse and, for many aspects, unique components.




An **advanced production scheme** – the “**BCMS**” - was put in place in the PS


- RF cavities tuned at different frequencies play together to **compress, merge and split proton bunches**
- Beams **~30% brighter** than standard scheme



Stored energy per beam




B1 collimators IP7



p-p physics – machine availability

2016 was characterized by **unprecedented machine availability**:

- The machine was **available for operation 72% of the time** scheduled for physics
- Overall **Stable Beam efficiency of 49%** (to be compared to 36% in 2012, and 30% for the short production period in 2015)




Possible thanks to:

- **Professionalism, commitment** and **attention to the details** from all the different **equipment groups**
- **Solid understanding** of the machine and beam behaviour
- Continuous effort in **fault and availability tracking**

p-p physics – summing all up

Combination of high **peak performance** and excellent **machine availability**

→ quite impressive progression of the **integrated luminosity**





~40 fb⁻¹

for ATLAS and CMS

(2016 target was 25 fb⁻¹!)

p-p physics – ALICE and LHCb

... acquiring data with **luminosity levelled at their desired values** all along the p-p fills




Where are we? 1/2

- Mature performance of injectors
- Good operational efficiency and flexibility
- Remarkable reproducibility
- Good beam behaviour (with these intensities)
 - Stability
 - Transmission through the cycle
 - Luminosity lifetime
 - Emittance growth
- Continue to worry about electron cloud

Where are we? 2/2

- Excellent availability in 2016 – it can be done
- Mature system performance
 - Quench protection, RF, Cryogenics, transverse damper, Power converters, Collimation, instrumentation, Controls, beam dump system, injection....
 - Improved functionality, diagnostics, understanding
- Premature dumps significantly reduced
 - UFOs, Radiation to electronics
- Machine protection
 - excellent as always

Schedule



- EYETS – Extended Year End Technical Stop – CMS pixel upgrade
- Pb-Pb end 2018
- Considerable special physics runs to be slotted in (90 m, 5 TeV pp, low energy high beta* ...)

Run 2 - objectives

- Deliver 100-120 fb⁻¹ to GPDs, keep ALICE, LHCb, TOTEM, ALFA, AFP happy
- Keep pushing performance and availability
- Look forward to HL-LHC without compromising present performance:
 - Optics (ATS), beta* levelling, LRBB compensation, RF full de-tuning, electron cloud...
- Look forward to the post-LS2 LIU era and how to exploit the potential
- Prepare for 7 TeV operation (but don't go there)

2017


- Another production year
 - Late start – no ions
 - **Target 45 fb⁻¹** to ATLAS & CMS at 6.5 TeV
- Machine configuration
 - Deploy HL-LHC optics
 - Start with beta* = 40 cm, maybe 33 cm later
 - 25 ns BCMS nominal bunch intensity
 - **2016 hardware issues resolved**
 - Max. luminosity $\sim 1.75 \times 10^{34} \text{ cm}^{-2}\text{s}^{-1}$ – limit cooling capacity of inner triplets

Continue to wrestle with electron cloud

HL-LHC - goals

- Prepare machine for operation beyond **2025 and up to ~2035**
- Operation scenarios for:
 - total integrated luminosity of **3000 fb⁻¹** in around 10-12 years
 - an integrated luminosity of **~250 fb⁻¹ per year**
 - $\mu \leq 140$ (peak luminosity of $\sim 5 \times 10^{34} \text{ cm}^{-2} \text{ s}^{-1}$)

LHC / HL-LHC Plan



HL-LHC - how?



- **Lower beta* (~20 cm)**
 - New inner triplet magnets - wide aperture Nb₃Sn
 - Large aperture NbTi separator magnets
 - Novel optics solutions
- **Crossing angle compensation**
 - Crab cavities, long-range beam-beam compensation
- **Dealing with the regime**
 - Collision debris, high radiation
- **Beam from injectors**
 - High bunch population, low emittance, 25 ns beam

HL-LHC: key 25 ns parameters

Protons per bunch	2.2×10^{11}
Number of bunches	2748
Normalized emittance	2.5 micron
Beta*	20 cm
Crossing angle	510 microrad
Geometric reduction factor	0.369
Levelled luminosity	$5.32 \times 10^{34} \text{ cm}^{-2}\text{s}^{-1}$
Levelled <pile-up>	140

Other variations are considered (BCMS, 8b+4e)

The largest HEP accelerator in construction



Dispersion Suppressor (DS) in P7

Modifications

1. In IP2: new DS collim. in C.Cryost.
2. In IP7 new DS collimation with 11 T

Cryogenics, Protection, Interface, Vacuum, Diagnostics, Inj/Extr, Controls, new UG and surface infrastr.

Matching Section (MS)

Change/new lay-out

1. TAXN
2. D2
3. CC
4. Q4
5. Correctors
6. Q5
7. Q5@1.9K in P6
8. New collimators


Interaction Region (ITR)

Complete change and new lay-out

1. TAXS
2. Q1-Q2a-Q2b-Q3
3. D1
4. All correctors
5. Heavy shielding (W)

> 1.2 km of LHC !!

Project structure



Project status

- 2016 (June Council): formal approval of the entire HL-LHC project
- 2016 June-August: re-baseline of the project
- 2016 2nd Cost & Schedule Review with full endorsement of new baseline cost

Re-baseline:

- Identification of the all possible savings, with reasonable impact on performance and availability, reducing the levels of redundancy/mitigations
- Keep reversibility (possibility to recovery the missed hardware later on)



2

CIVIL ENGINEERING


2 new 300-metre service tunnels and 2 shafts near to ATLAS and CMS.



3

"CRAB" CAVITIES

16 superconducting „crab“ cavities for each of the ATLAS and CMS experiments to tilt the beams before collisions.



1

FOCUSING MAGNETS


12 more powerful quadrupole magnets for each of the ATLAS and CMS experiments, designed to increase the concentration of the beams before collisions.

ATLAS

ALICE

CMS

LHCb



6

SUPERCONDUCTING LINKS


Electrical transmission lines based on a high-temperature superconductor to carry current to the magnets from the new service tunnels near ATLAS and CMS.



5

COLLIMATORS

15 to 20 new collimators and 60 replacement collimators to reinforce machine protection.



4


BENDING MAGNETS

4 pairs of shorter and more powerful dipole bending magnets to free up space for the new collimators.

One focus of attention at the moment: civil engineering contract


- 19 April: Market survey short list
- 30 June: Issue Invitation to tender
- March 2018: Finance committee

Process is being closely monitored!




Plus Point 1 and surface buildings in 1 & 5

The Inner Triplet region with in-kind



The MS region with in-kinds



Recent LARP Achievements – Magnets (2)



MQXFPM1 (4m) Coil in Mirror Configuration at BNL

- Two training quenches at 1.9K on Oct 31st 2016
 - Quench #1: 14.386 kA
 - Quench #2: 16.040 kA
 - Power supply failure at discharge of Quench #2.



DOE Guidance after July '16 LARP Review

1. With respect to the superconducting quadrupole magnets we are impressed and pleased with the progress of the models for the Hi-Lumi quadrupoles as demonstrated by the tests at Fermilab earlier this year. We have given revised funding guidance to LARP/Hi-Lumi

look forward with great anticipation to receive the results of the testing of the 4 meter long prototype quadrupole next spring.


MQXFPM1 (4m) Prototype Coil under assembly at FNAL, BNL and LBL

Major Milestones in 2016/17

Several novel concepts designed/developed to meet HL-LHC needs,
Prototyping of all critical items where possible



SPS Tests Program – Weekly Schedule



Cryomodule delivered to SPS on 22nd Jan'18
 Vacuum & cryo validation in SM18, RF tests insitu

LHC Injector Upgrade (LIU)

Main means to achieve the target HL-LHC proton beam parameters

Linac4 in for Linac2	<ul style="list-style-type: none">• H⁻ injection into PSB at 160 MeV• Expected double brightness for LHC beams out of the PSB
Booster	<ul style="list-style-type: none">• Increase energy to 2 GeV• New RF system• New main power supply
PS	<ul style="list-style-type: none">• Injection at 2 GeV• Beam production schemes• Feedback systems: new wide-band longitudinal feedback; transverse feedback against head-tail and e-cloud instabilities
SPS	<ul style="list-style-type: none">• Power upgrade of the main 200 MHz RF system• Electron cloud mitigation through a-C coating (baseline) or beam induced scrubbing


Many other options plus a full ion upgrade program

Deployment: 2019 - 2020

LHC - conclusions

2016 - **memorable year** for CERN and the LHC

- **Reached design luminosity** and exceeded it by 40%!
- While maintaining **Stable Beams efficiency of ~50%!**
- ...plus $\beta^*=2.5$ km, proton-ion, machine developments...



Looking good for
the next 2 years
(usual caveats)

HL-LHC Conclusions

- Fully approved and re-baselined
- Significant international technical effort on all fronts
- Critical civil engineering contract process is in progress...

***We are now heading for construction:
All WPs are manufacturing models
and prototypes. The boat is sailing...***