

# **4-year overview**

**Huan Zhong Huang**  
**For UCLA Experimental Group**

**January 10, 2025**

# Groups members: current and past

## Graduate students

current: **Thomas Marshall, Xiatong Wu, Yunshan Cheng, Aditya Dash & Maria Sergeeva**

previous (& current location): **Zhiwan Xu (LANL)**

## Postdocs

current:

previous (& current location): **Zhongling Ji (Syracuse/Jlab)**

## Undergrads

current: **Nihal Gozluoglu Karakus, Lyra Yi**

previous (& current location):

**Staff: Oleg Tsai, Gang Wang and Huan Zhong Huang**

# List main accomplishments in past 4 years

- Spearhead design of fEMCal for ePIC. From conceptual to final design review scheduled in spring 2025.
- Coordinated efforts in developing TDR, with Version 1 released to ePIC collaboration in December 2024.
- Carry out the eRD106 to finalize the design of fEMCal, eRD106 will be completed in Feb 2025.
- Coordinated successful final design reviews for SiPMs and scintillation fibers (CD3A, CD3B).
- Coordinated efforts in developing calorimetry concepts for ATHENA detector.
- Developed the GEANT description of the fEMCal detector

# Detector construction plans at campus/lab

- **UCLA group will coordinate overall efforts to build fEMCal.**
- **UCLA is a construction site to receive and certify all scintillation fibers for fEMCal.**
- **UCLA electronics shop will produce all SiPM boards.**
- **UCLA students/staff will test/calibrate all SiPM boards.**
- **UCLA staff will oversee installation/integration and commissioning of fEMCal in ePIC**

# Key roles in ePIC

- Huan Z. Huang and Oleg Tsai are serving as DSLs for fEMCal.
- O.Tsai is serving as technical coordinator for fEMCal.
- O.Tsai is serving as co-convener for ePIC calorimetry WG.

## Previously

- O.Tsai served as co-convener of joint ECCE and ATHENA calorimetry WG.
- O.Tsai served as co-convener of ATHENA calorimetry WG.

# Key non-EIC accomplishments

Worked on sPHENIX EMC construction

Participate in the sPHENIX EMC calibration effort

## STAR

CME upper limit from isobar collisions

CME related charge separation from BES II data

EM field effect on directed flow of charged particles

CMW searches and background studies


Hyperon directed flow and hyperon-K correlations

## sPHENIX


Heavy flavor physics program

# 3-4 EIC highlights with pictures (multiple slides)

**Table 8.44:** Some requirements on performance of fEMCal and its parameters



Parameter	Requirements	Comments
Geometrical Acceptance	$1.4 \lesssim \eta \lesssim 3.9$	$R_{out} \sim 190$ cm, $Z_{front\,face} \sim 341$ cm Hole for the beam pipe $30 \times 30$ cm <sup>2</sup>
Integration envelope	$R_{max}=205$ cm, Depth = 27 cm	
$E_{min}$ in a single tower	15 MeV	Minimal shower energy 50 MeV
$E_{max}$ in a single tower	100 GeV	$18 \times 275$ GeV, ep
Maximum rate in a single tower	10 kHz	$E_{thr}=15$ MeV, $10 \times 275$ GeV ep 500 kHz collision rate
Radiation doses	15 kRad	Integrated over 10 years
Neutron fluxes	$4 \times 10^{11}$ n/cm <sup>2</sup>	1 MeV eq, integrated over 10 years
Energy resolution	$\lesssim 12\%/\sqrt{E} \oplus (2)\%$	Verified in the test beams
$\gamma/\pi^0$ separation	up to 50 GeV	$\sim 5\%$ mis-identification at 50 GeV
Depth	$23 X_0$	Minimize leakages
Detector parameters	Units	Comments
$X_0, R_m$	7 mm, 19 mm	Rad. length, Moliere radius
$f_{samp}$	2%	$e/h \simeq 1$ above 10 GeV
Scintillating Fibers	$\varnothing$ 0.47 mm	Single clad sc. fibers
Light yield	$\sim 1600$ pixels/GeV	Test beam results.
Transverse size of tower	2.5 cm $\times$ 2.5 cm	Matches $R_m$
Transverse size of installation block	10 cm $\times$ 10 cm	Block of 16 towers
Total number of towers	18320	
Photodetector	S14160-6015PS	Four $6 \times 6$ mm <sup>2</sup> SiPMs per tower 15 $\mu$ m pixels size
Monitoring system	Blue LED	LED integrated on SiPM board. One LED per four towers



**In preparation for Final Design Review, detailed detector engineering modeling. Table with detector parameters from TDR.**


# Forward EMCal progress 2023-2024



- Mounting scheme on fHCal designed.
- Structural Tests completed



- Installation tooling designed
- Installation procedures verified



- Prototyping of readout integration is in progress



- Refining of production methods is in progress



June 2nd, 2021

Director's Review

X. Dong




# Major forward EMCAL progress in 2024



Forward Emcal installation block at FNAL

## Readout:

- SiPM board designed and ~ready to produce prototypes
- FEB layout in progress, ~20% complete
- FEB - RDO interface scheme defined.
- Power cable group definitions & rack space requirements in progress.
- Initial round of COTS DC/DC and SiPM radiation testing completed (UC Davis 64 MeV protons, May 2024)



UC EIC Students at FNAL.

- New highly efficient and compact light guide designed.
- Production method established.

Test Run at FNAL completed (06/13/2024)

Goals to measure:

- Absolute Light Yield
- Uniformities of response

Data analysis is in progress.

# Leveraged funding (grants due to MRPI project)

**eRD106 ~ \$77k**

**DOE support of 50% post-doc for three years ~ \$135k**

**EIC support of UCLA staff ~ \$100k**

# Publications in past 4 years

- **Science Requirements and Detector Concepts for the Electron-Ion Collider: EIC Yellow Report. Nucl. Phys. A 1026 (2022) 122447**
- **ATHENA Detector Proposal -- A Totally Hermetic Electron Nucleus Apparatus proposed for IP6 at the Electron-Ion Collider. JINST 17 (2022) 10, P10019**

# Future plans in the EIC program

- Finalize design of the fEMCal, produce TDR.
- Lead the fEMCal team through series of reviews toward construction phase.
- Complete the construction/installation/commissioning of the detector.

Work on simulations of physics measurements using the forward EMCal+Hcal+Tracking

Topics: forward jets/heavy flavor physics  
3D image of the nucleon and nuclei

---

# Backup