



## 1. Introduction

The EIC (Electron Ion Collider) experiment, ePIC will be constructed and commissioned at P6 in BNL. This presents a low jitter and phase deterministic CLOCK, and synchronous CONTROL distribution system to the front end electronics. The design, some test results, and near-future plans are presented.




	ESR	HSR
RMS bunch length $\sigma_z$ (mm/ps)	7-9/23-30	75-60/250-200
Electron Beam Energy: 5 – 18 GeV		
Proton Beam Energy: 41, 100, 275 GeV		
Luminosity: $10^{34} \text{ cm}^{-2}\text{s}^{-1}$		



## 2. Hardware description

### 2.1 The diagram of ePIC DAQ, Clock /Control distribution electronics



### 2.2 Hardware description

#### GTU: Global Timing Unit

control encoding, status decoding.  
The interface for machine clock source, Data acquisition control and monitor etc.

#### DAM: Data Aggregation Module:

The clock/control fanout, and status/busy accumulation.  
local control over the RDO boards connected, though the main function of the DAM is for Data Acquisition.

#### RDO: optical interface of detector ReadOut

control decoding, status encoding.  
The clock/control interface to the front end electronics.  
Data collection from Frontend boards, and data transmission to the DAM

#### FEB:

Detector dependent Front End / ASIC carrier boards.


\* The presenter would like to thank everyone in the Nuclear Physics community and High Energy Physics community that make this poster possible.



## 3. Clock Distribution

### 3.1 Dedicated fibers between GTU and DAM (and maybe RDO)

The GTU recovers the 98.5 MHz EIC beam crossing clock as the ePIC system clock. The clock is fanned out using ultralow jitter clock chips and optic transceivers on the GTU. The clock is received by the optic transceivers, and jitter cleaned and fanned out to the MGTs (Multi Gigabit Transceivers) on the DAM.




\* GTU to monitor the feedback clock phase

### 3.2 MGT serialized data between DAM and RDOs

The GTU\_CONTROL (8-bit) and DAM\_CONTROL (32-bit) are serialized and phase aligned with the System clock (98.5 MHz) on the DAM (fiber DOWNLINK).

The RDO reconstructs the system clock, and sends front-end electronics data and status back to the DAM (fiber UPLINK).



\* DAM to monitor the MGT\_RxREClk phases

## 4. Synced CONTROL Distribution

### 4.1 Fixed latency from GTU to DAM, and RDO

The fibers from GTU to DAM will be the same length/delay routed in the DAQ computer racks. The fiber delays from DAM to RDO will be measured individually, and saved on the RDO. The RDO will delay the received GTU control commands (compensating for the fiber latency), so that all the RDOs will send the GTU commands at the SAME time (synchronous with the 98.5 MHz system clock).


### 4.2 Beam orbit information is embedded in GTU control command

The GTU, DAM and RDO will all keep (at least) two counters, Beam Crossing counter (11-bit from 1 to 1260), and Beam Orbit counter (at least 5-bit, for a total time period of about 400 μs)


The GTU will send SRO (Streaming ReadOut) time window start command and some other SYNC commands on the first beam crossing of the orbit. The size of RDO time window can be set on the GTU.

### 4.3 DAQ data flow control

There are data buffers on DAMs and RDOs. The buffer status is monitored by GTU, DAM and RDO.




Beam Crossing phase aligned Beam orbit phase aligned



## 5. Some Test results


### 5.1 Test setup:

Skyworks' Si5344H → System Clock, Reference  
BNL's FLX182 as DAM;  
OpalKelly's XEM8320, Xilinx KCU105/Skyworks' Si5394A as RDO



### 5.2 (RDO's) RxREClk Test setup:

The clock jitter is measured by the positive width and the negative width of the difference between the RxREClk and the reference clock using the Tektronix's MSO64 oscilloscope.




RxREClk jitter < 3 ps  
RxREClk phase can be fixed at ~ (0)ps precision (by measuring the phase difference between the RxREClk and the pseudoClock, and resetting the RxREClk CDR.)

## 6. Status and Future plans


### 6.1 Proved designs by others

TJNAF's 12 GeV upgrade program proved that the dedicated clock distribution and the DAQ (BUSY) feedback are viable.

### 6.2 Pre-prototype RDO is being manufactured



### 6.3 Prototype FLX155 (ePIC DAM) is expected this year



### 6.4 To setup a sub-system DAQ (DAM + RDOs) to fine tune the protocols, to think about GTU prototyping

Notice: Authored by Jefferson Science Associates, LLC under U.S. DOE Contract No. DE-AC05-06OR23177. The U.S. Government retains a non-exclusive, paid-up, irrevocable, world-wide license to publish or reproduce this manuscript for U.S. Government purposes.