


APS-U Accelerator Controls System Update




PRESENTED BY KAREN WHITE FOR APS-U CONTROLS

Advanced Photon Source
Argonne National Laboratory



09-14-2022

APS & APS-U Overview


- APS Accelerator Complex & its Upgrade



APS double bend lattice



APS-U multi-bend achromat lattice



~70-fold reduction in horizontal emittance


APS-U Controls System Architecture

- Standard 3-tier distributed structure with EPICS7 as software framework

Archiving, Alarm Management,
Strip charts, Save/Restore Utility



High Performance
Storage




Overview of APS-U Controls System

APS-U Controls High Level Applications

- EPICS 7 Waveform/Image Viewer
 - EPICS 7 sdds-epics toolkit enhancements
 - Process Variable Directory & Name Service
 - Infrastructure Monitoring
 - High Level Applications for Specific Systems (e.g. orbit, synchronous PS setpoint, post-mortem, ...)
- < Project-wide Tools >**
- Component Database
 - eTraveler
 - Cable Management Application

APS-U Control System Infrastructure (+ MPS)


- Double-sector Infrastructure
- Timing / Fast Event System
- VME chassis (for legacy modules)
- Serial-to-Ethernet ports
- Tier 3 Network Switches
- EPICS 7 PVA Gateway (collaboration assistance)
- VLAN & PV Gateway Design & Implementation
- Servers
- Machine Protection System (MPS) system)
- DAQ (time-correlated data acquisition system)



Not on Project

Operations Tools

- Display Manager
- Alarm Handler
- Data Logger
- Operations Logbook
- Save/Restore



APS-U Technical System Interfaces

- Unipolar Power Supplies + DAQ
- Bipolar Power Supplies + DAQ
- Vacuum Systems + Beam Dumps
- Bunch Lengthening System Interlocks/LLRF + DAQ
- BLS Cryo-system + Distribution
- Injection/Extraction + DAQ
- RF BPM (Libera) + DAQ
- X-Ray BPM + DAQ
- X-Ray Intensity Monitor
- BPLD
- Beam Size Monitor (absolute)
- Beam Size Monitor (relative)
- Mechanical Motion System
- DCCT
- Bunch Current Monitor
- Fast Orbit Feedback + DAQ
- Longitudinal Feedback + DAQ
- Transverse Feedback + DAQ
- Booster/SR 352MHz Timing
- Slow Abort Sequencer

Database Applications

- CDB, CDB/Cable, eTraveler are actively supporting project construction
 - CDB Mobile application provides sufficient flexibility to support in field work
 - Some statistics of data entry

❖ CDB:

- Registered Users 341
- Catalog Items 2,706
- Inventory Items 33,841
- Machine Elements 30,391
- MAARC Items 163,063

❖ Cable:


- Cable Catalog Items 176
- Cable Inventory Items 2,365
- Cable Design Items 11,875

❖ eTraveler

- Registered Users: 287
- Draft Forms: 703
- Released Forms: 960
- Active travelers: 18,564
- Finished travelers: 12,825
- Archived travelers: 7,418


Inventory Item Tracking in CDB

Function Name	Project Name	Catalog Name	Tag	QR ID	Inventory Id	Location1	Inventory Hyperlink	Status
			Unit: 4	2852	3718	400	View Item	Installed
			Unit: 2	2850	3716	400	View Item	Installed
			Unit: 1	2213	2922	400	View Item	Installed
Controller - Motor	APS-U Production	Horizontal Collimator Controller Chassis	Unit: 0001	Null	196716	No Data	View Item	Planned
			Unit: 0005	24691	250519	No Data	View Item	Planned
			Unit: 0004	24690	250518	No Data	View Item	Planned
			Unit: 0003	24689	250517	No Data	View Item	Planned
			Unit: 0002	24688	243383	No Data	View Item	Planned
			Unit: 0027	33261	107989	L2109	View Item	Ready For Use
CPU	APS-U Production	MVME2500 CPU	Unit: 0028	33262	107990	L2109	View Item	Ready For Use



EPICS 7 Waveform/Image Data Viewer (C2DV)

- C2DV: A Python based data visualization tool for EPICS 7 high speed DAQ system
 - A scope viewer for plotting PVA waveforms
 - An image viewer for displaying streaming Area Detector image data over PVA
 - A striptool for monitoring CA and PVA scalar PVs



Scope viewer





Image viewer




Striptool

Other High-Level Applications

- A web-based naming system, which was developed originally at FRIB, has been introduced to manage the APS-U naming convention
 - 600+ name entries captured in the naming system
- OpenNMS was selected to monitor controls system infrastructure
- Olog is deployed as next logbook management system
 - Existing Controls logbook data has been migrated into this system now
- Logging as well as IOC console message to be logged into ElasticSearch using logstash, and browse it on Kibana

EPICS Module Configuration, Build, and Management


- Using Conda for software environment management including EPICS
- Adopted 'Sumo' package to automate IOC modules configure/build
 - Sumo (HZB/BESSY) to build IOC support modules from source on demand
 - All source comes from APS' GitLab server
 - IOC applications will specify needed support modules and versions
 - Sumo is used similarly to create private module build areas to assist development
 - Where appropriate we hope to include PLC, FPGA, and DSP code in the same environment
 - We are developing against an EPICS 7 release



This block contains three screenshots. The left and middle screenshots show the 'U:S27:BPSC2 Bipolar PS Controller' and 'U:S28:BPSC2 Bipolar PS Controller' control panels, displaying system info, RTFB events, and temperature data. The right screenshot shows a terminal window with a log of commands and responses, including a reboot sequence and various data reads.



APS-U Time-Correlated DAQ System

- Architecture



DAQ System Simulation Environment

- In order to run the DAQ system in different test environments, several simulation tools were developed including data source simulator and data collector simulator
 - Data source simulator: simulate the hardware that generates and sends data to a specific DAQ IOC. The simulation generates simple linear data with noise to easily verify that the data was processed correctly
 - Data collector simulator: captures PV objects published by the DAQ IOC, and save the data into a local file in desired format like HDF5, or other site-specific data format (e.g. Self-Describing Data Sets [SDDS] at APS)



C2DV Client

APS-U Time-Corelated DAQ System

- DAQ Hardware



DAQ Linux Servers

Fully assembled DAQ aggregator FPGA chassis



PS DAQ aggregator FPGA chassis



TBT DAQ aggregator FPGA chassis



Example of DAQ Linux Servers installed

APS-U MRF Fast Event/Timing System


- New timing system with MRF 300-series hardware
 - Event Link distributed to 232 technical systems
 - 113 + Individual Triggers (TTL) to technical systems

Generator	Receiver	Fanout	Rear Transition	TTL Input	TTL Output
33	41	45	9	31	162

- Jitter measured relative to event clock reference at APS

	UNIV Output		CML Output	
PLL Bandwidth	RMS	Pk-Pk	RMS	Pk-Pk
MH (375 Hz)	16.15 ps	101.56 ps	8.70 ps	78.13 ps

- Fully use delay compensation function to compensate the time delay in the fibers
- A few testing stands setting up
 - In Diagnostics lab, supporting RF BPM acceptance test
 - Along SR mezzanine floor
 - In installation preparation warehouse




VME-EVM-300



VME-EVR-300




VME-FOUT-12



Testing Setup along SR Mezzanine Floor

APS-U MPS and BPLD System

- System Architecture



APS-U MPS and BPLD System

■ System Hardware



Main MPS Chassis



Local MPS/BPLD Chassis



MPS Chassis Power Supply




*Fully populated MPS stand under integration testing
Left to right:*

- MPS chassis rack #1,*
- MPS chassis power supply rack,*
- electronics rack (BPM, MRF timing, network, etc),*
- MPS chassis rack #2*
- MPS chassis rack #3*

APS-U Accelerator Network

■ Architecture



Tier-1 to Tier-2
• 200Gbps

Tier-2 to Tier-3
• 50Gbps (2x25Gbps)

Tier-3 to electronics
• Gbps
• 10Gbps


APS-U Accelerator Network

■ Network Infrastructure Status

- APS-U network installation finished, including its fibers
- Network subnet/VLAN (total 31 VLAN) design finished, implemented, and ready to use

Vlan Name (32 max)	Max Hosts	DHCP
MCR-Workstations	250	yes
DAQ-Servers	64	yes
MPS	250	no
Accelerator-Timing	250	no
Injection-Extraction-System	125	no
Spark-BPM-DAQ-System	250	yes
RF-BPM-Libera-Brilliance	250	yes
RF-BPM-Spark	250	yes
BSM-Motion-XBPM	250	no

Example APS-U accelerator VLAN implemented and ready



Tier-3 Network installed

Summary

- APS-U is under active construction and preparation for its dark time starting from April 2023
- Database application like CDB, Cable, as well as eTraveler system plays critical role to support the project
- EPICS7 based time-correlated DAQ system capable to stream data over pvAccess with data rate higher than 3GB/s, which is gaining more and more interesting in supporting beam commissioning and future operation
- MRF 300-series based timing system, with lots of new functions enhanced to meet APS-U needs including full functional delay compensation capability
- The MPS/BPLD system starts with a star connection topology with future extendibility to a ring structure
- A high-performance network with 31 VLAN in place to meet various needs
- Installation started in the place where suitable including network as well as rack mounted DAQ computer server